KOLAR DIVISION.

Notice.

The attention of the public is invited to the Notification published in Gazette No. 31, dated the 3rd August 1916, page 560, calling for tenders for constructing Police Station and Lines at Sugatur.

Notice.

The attention of the public is invited to the Notification published in Gazette No. 31, dated the 3rd August 1916, page 561, calling for tenders for restoring the Nambihalli Tank, Registered No. 74 of Srinivaspur Taluk.

V. AYASWAMI IYER,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 5th August 1916.

It is hereby notified that sealed tenders will be received from the Firms whose name has been registered by the Government of Mysore at the Office of the Executive Engineer, Shimoga Division, till 5 P.M. of 8th November 1916 for the supply of the undermentioned articles, to be suppled at the stipulated rates in quantities for which orders may be issued from time to time during the year 1916-17.

Rs. 100 is required to be deposited as earnest money.

Samples of the best articles of each class, may be supplied while tendering.

The Firms that tender are requested to supply the articles needed within the limits of time noted opposite the kinds of orders, *viz.*:—

(*a*) Orders under Rs. 500 to be filled up and consignments despatched before the evening of the 2nd day of the receipt of the order.
(*b*) Between Rs. 500 and 2,500 before the 7th day after the receipt of the order.
(*c*) Between Rs. 2,500 and 5,000 before the 15th day after the receipt of the order.
(*d*) Above Rs. 5,000 according to the time fixed by mutual agreement though in the case of orders of all the other three classes noted above the time limit fixed may be altered by mutual agreement.

If any Firm does not supply the articles and intimate despatch within the time limit fixed herein or by mutual agreement without further notice, the Public Works Department will purchase the articles required from any other Firm at the risk of the Firm whose tender has been accepted.

Approval of tenders will be intimated by the undersigned.

The approval of tenders and orders based on tenders rests with the Executive Engineer if the value of each order is less than Rs. 5,000 and by the Superintending Engineer if between Rs. 5,000 and Rs. 10,000 and if over Rs. 10,000 by the Chief Engineer.

The articles likely to be needed during the current official year are as noted below.

The quantities noted are approximate and cannot be guaranteed.

The Firm whose tender is approved has to supply whatever quantity is ordered during the year whether more or less.

The names of articles likely to be required during 1916-17 are :—

Cast iron pipes spiget and socket turned and bored ends 9" dia. ...	100	
Pick axes	200	
Mamties	200	
Round iron bars $\frac{3}{4}$" (average each 15' long)	500	
Cement casks	100	
Roofing tiles	50,000	
Flooring tiles	12,000	
Diagonal tiles	1,000	
Rectangular half tiles	3,000	
Ridge tiles	2,000	
Ventilating tiles	100	
Galvanised iron sheets corragated 3' long of various gauges ...	200	
Plain zinc sheets 7' × 3' of various gauges	50	
Teakwood scantlings and planks	2,000	C. ft.
Teakwood in logs	3,000	"
Honne or nandi scantlings and planks	1,000	"
Honne or nandi logs	1,500	"
Reepers, teakwood	100,000	R. ft.
Sundry articles to the value of Rs. 1,000.		

N. B.—The prices should be quoted in terms of the unit specified.

Dated 7th August 1916.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 5 P.M. of 5th September 1916, for constructing Police Station and Lines at Kodur, Nagar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1917.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 350 (three hundred and fifty) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Police Station and Lines at Kodur, Nagar Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

No.	Items of work	Per	Quantity
1	Clearing site and levelling ground	Lump sum	
2	Earthwork excavating foundation and filling in basement	C. yd.	52
3	Stone in mud, foundation and basement	C. ft.	2,054
4	Burnt brick in mud, superstructure	"	2,244
5	Do in mortar	"	637
6	Burnt stone slabs, neatly dressed	S. ft.	308
7	Plastering with mortar	Sqr.	63·05
8	White and colourwashing	"	63·05
9	Honnewood work wrought and put up	C. ft.	84·10
10	Roofing with first class Mangalore tiles on teak reepers, etc., complete ...	Sqr.	16·65
11	Ridge tiles, set in mortar	R. ft.	48
12	Flooring with 3" concrete and cement plastered	Sqr.	9·82
13	Honnewood battened doors, with fittings, complete	S. ft.	234
14	Do windows, with ordinary shutters and iron bars, of ¾" dia. with fittings, complete.	"	35
15	Do ventilators, with ¾" iron bars and complete	"	15
16	Do ornamental eave board with chocolate painting ...	R. ft.	258
17	Taring to wood work	Lump sum	
18	Chocolate painting with varnish coating	Sqr.	6·58
19	Pointing with mortar for basement	"	2·83
20	Providing out let pipe 1½" dia.	Each	8
21	Flooring with gravel including consolidation ...	C. yd.	8
22	Providing smoke escapes	Each	4

Dated 10th August 1916.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 5 P.M., of 10th September 1916 for restoring Nagathibelagalu Tank, Registered No. 139 of Shimoga Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1916.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred and twenty only (Rs. 120) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Nagati Belagalu Tank, Shimoga Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed abstract estimate of restoring Nagati Belagalu Tank, Registered No. 139, Shimoga Taluk.

Items of work	Per	Quantity
Bund R. L. 54·00.		
Jungle clearing and removing roots on bund	Lump	sum.
Earthwork to bund including watering and tamping	C. yd.	8,937
Turfing	Sq.	994·55
Grade stones with bed and index stones	Each	28
Bench mark stones	"	2
Year and tank register number stone	"	1
Gauge stone with bed slab	"	1
Sluice No. II.		
Earthwork cutting and refilling bund with watering and tamping...	C. yd.	105
Metal concrete in surki mortar	C. ft.	113
Brick concrete in surki mortar	"	52
Burnt brick in surki mortar	"	88
Plastering	Sqr.	1·00
Stone ware pipes 6" diameter including carting, etc., complete or cast iron.	R. ft.	55
Cement pointing to joints of pipes	Lump	sum.
Plug with rod, complete	Each	1
Sluices No. I and No. III.		
Lump sum	Lump	sum.
Natural waste weir 50 feet long.		
Clearing and forming site	Lump	sum.

N. B.—Royalty to be paid by contractor. Materials supplied by Government should be taken at Government rates and used.

V. R. NIJAGAL,
Executive Engineer.

RANGE FOREST OFFICE, CHANNAGIRI.

Notification dated 4th August 1916.

It is hereby brought to the notice of the public that the marginally noted unclaimed teak pieces fit for Tellows which were found lying in the Gavadukatti village, Channagiri Taluk, are now in the custody of the Department at Joladhal Lodge. Claimants, if any, for that property should apply to the Range Officer, Channagiri within one month from the date of notification, failing which the timber will be confiscated to Government.

	No.	C.ft.
Teak pieces ...	21	33

N. CHINNIAH CHETTY,
Sub-Assistant Conservator,
Channagiri Range.